



**CITY OF CORONA  
ADMINISTRATIVE SERVICES DEPARTMENT  
PURCHASING DIVISION**

---

October 18, 2016

**SUBJECT: Notice Inviting Bids 17-023CA, Project No. 71610217**

**ADDENDUM No. 1  
City Park Basketball/Volleyball Court Addition**

The Purchasing Division of the Administrative Services Department has relocated to the third floor at City Hall, 400 S. Vicentia Avenue, Corona, CA. This Addendum No. 1 to the subject Notice Inviting Bids revises the suite number where bidders are required to submit their sealed bids, provides a Water Quality Management Plan and drawing revisions. Please note the bid due date and time remains unchanged.

All provisions of and attachments to this Addendum No. 1 are hereby incorporated by reference into the subject NIB. Bidders shall account for all provisions pursuant to this Addendum No. 1 in submitting their bids. Each bidder shall acknowledge receipt of this Addendum in their Bid in the spaces provided therein.

**1. Contact Documents Revision:**

- 1.1 Notice Inviting Bids, paragraph 1, page 1 is hereby deleted in its entirety and replaced with the following:

The City of Corona Administrative Services Department – Purchasing Division (“City”) will receive sealed bids for NIB No. 17-022CA, City Park Basketball/Volleyball Court Addition, Project No. 71610217 at the City of Corona Administrative Services Department, Purchasing Division Office, 400 South Vicentia Ave., **Suite 320**, Corona, CA 92882 no later than **October 25, 2016, 2:00 p.m.**, at which time or thereafter said bids will be opened and read aloud. Bids received after this time will be returned unopened. Bids shall be valid for 60 calendar days after the bid opening date. Bids must be submitted on the City’s Bid Forms. (The City does not provide an option for electronically submitted bids.)

- 1.2 Contract, ARTICLE 2. TIME FOR COMPLETION, is hereby deleted in its entirety and replaced with the following:

**ARTICLE 2. TIME FOR COMPLETION.** A Move-in period of **10 calendar days** shall start on the date of issuance of the Notice to Proceed. This period shall be used by the Contractor to confirm utility locations, turn in project submittals or other supporting documentation for approval and procure the necessary material and equipment to complete the Work. The Work shall commence on the last day of the Move-in period or the first Working Day the Contractor actually starts the Work, **whichever occurs first**. The Contractor shall complete all Work required by the Contract Documents within **100 Working Days**. By its signature hereunder, Contractor agrees the time for completion set forth above is adequate and reasonable to complete the Work.

2. **Drawing Revisions:**

2.1 **Drawing L3 - Replace Note 4**

Detail E, Note No. 4 is revised to include the diameter of the steel dowel. The note has been revised as follows: **“24” Steel Dowel with 0.50-inch diameter, unless otherwise approved by DWP, core existing concrete and epoxy in place prior to the pouring of new concrete.”**

2.2 **Drawing L8 – Replace Existing Tree Note**

Project Legend, the last Existing Tree Note is revised to clarify the maintenance of trees within the limits of contract work. The note has been revised as follows: **“Protect existing trees and other vegetation indicated to remain in place, against unnecessary cutting, breaking or skinning of roots, skinning or bruising of bark, smothering of trees by stockpiling construction materials or excavated materials within drip line, excess foot or vehicular traffic, or parking of vehicles within drip line. Water trees and other vegetation to remain within the limits of contract work as required by the project Engineer to maintain their health during course of construction operations”.**

2.3 **Drawing L8 – Replace Demolition Note 5**

Demolition Note No. 5 is revised to eliminate the “Return to the City” language and include the disposal of all railroad ties. The note will read as follows: **“Remove and dispose of all existing railroad ties”.**

2.4 **Drawing L8 – Replace Demolition Note 6**

Demolition Note No. 6 is revised to include the removal of roots interfering with the construction of the project. Note No. 6 has been revised as follows: **“Remove turf, interfering roots, irrigation pipes, and rotors. Cap lateral lines and abandon in place. Dispose of turf and roots in a legal manner”.**

- 2.5 **Drawing L10 – Insert Construction Note 6A**  
Construction Note No. 6A is included to identify the addition of an ADA picnic table. The note shall read as follows: **“Quick Crete round concrete ADA picnic table model: QR-42FC-3, Color: C11 Adobe Taupe, Finish: T1 Smooth. Install per manufacturer’s recommendations. The location will be verified by the Engineer at the time of Construction”. The ADA picnic table, model QR-42FC3, shall be constructed per construction plan “Round Food Court Table (QR-42FC3)” attached hereto as Appendix B to this addendum.**
- 2.6 **Drawing L10 – Replace Construction Note 11**  
Construction Note No. 11 is revised to modify the model type for the waste receptacle that is to be used. The note has been revised as follows: **“Waste Container – Quick Crete Model: QS-PS 2532W-DCORO2”. The waste container shall be constructed per construction plan “Square Palm Series Waste Container” attached hereto as Appendix B to this Addendum.**
- 2.7 **Drawing L10 – Eliminate Construction Note 6**  
The quantity of Construction Note No. 6 exhibited on sheet L10 has been modified from 3 to 2 picnic tables displaying the elimination of one picnic table model # QR-42FC on the sheet. **The picnic table, model QR-42FC, shall be constructed per construction plan “Round Food Court Table (QR-42FC)” attached hereto as Appendix B to this Addendum**
- 2.8 **Drawing L11 – Replace first note under Turf Rotors – Pop-Ups**  
Notes and Legend have been modified to include symbols No. 22 and No. 29 with symbols 27, 28, 30, 31, and 33 in the first note under Turf Rotors – Pop-Ups. The first note under Turf Rotors – Pop-Ups has been revised to read as follows: **“Remove and dispose of existing rotor or spray head, cap lateral lines as necessary for proper continued valve operation if any heads remain on valve at limit of construction.”**

3. **Appendices:**

- 3.1 **Add Appendix A – Water Quality Management Plan**, dated February 10, 2015 in its entirety.
- 3.2 **Add Appendix B – Picnic Table & Trash Can Details**, (3) sheets, in their entirety.

Carol Appelt  
City of Corona  
Administrative Services Department  
Purchasing Division  
400 S. Vicentia Ave., Suite 320  
Corona, CA 92882  
951-279-3620